

Answers to Questions

Each question is referenced by the appropriate RFP page number(s) and section where applicable.

#	Page #	RFP Section Reference	Question	Answer
01	N/A	N/A	Please advise wood door veneer and finish required & provide specifications if available.	The doors will be solid core maple with finish to be factory stained in color selected from manufacturer's standard colors by the architect.
02	N/A	N/A	Will existing furniture be removed by owner?	Yes, All movable furniture will be removed by owner
03	N/A	N/A	Is any overtime required for the electrical panel replacement.	Yes, there will be overtime required for the work on a Saturday or afterhours on Friday for revising the new transformer and installing the new breaker in the existing electrical panel and circuiting all new circuits in the existing panel, since the current space being served by the electrical panel still need to be kept active on all times. Include at least 1-1/2 days of overtime for doing this work on the weekend.
04	N/A	N/A	Is a dust control barrier required	A temporary stud partition is to be constructed at the start of the construction period to control dust in the large open room which will remain in operation. Six mil polyethylene on studs to run the length of the new wall, fastened directly to studs. Dust control barrier can be removed as soon as the outside of the new wall is painted and the new door is installed. Partition to extend from floor to height of existing suspended ceiling. Staging for the work should take place within the enclosed area. Contractor to minimize tracking and insure a clean job site.
05				

